

Bid Addendum Report



Balan Bihul Rural Municipality

Balan Bihul Rural Municipality
Saptari
Saptari
Madhesh.Pradesh
Nepal

Addendum No: 1

Published On: 27-05-2026 15:00

Invitation No: BBRM/Works/NCB/02/2082/083

Dated On: 21-05-2026 00:00


लक्ष्मी कुमार साह
सब-इन्जिनियर
योजना

Following changes are made in the bid document



Chapter: General Information

Sl. No.	Relavant Clause No / Name	Existing Clause	Modified Clause
1	Clarification Submission Date	Not Provided in Bid Document	2026-05-27 15:00:00
2	Authorised Representatives Address	Saptari Saptari Madhesh Pradesh	Saptari Saptari Madhesh Pradesh


लक्ष्मी कुमार साह
सब-...
यो...



Chapter: Bill of Quantities

1 Provisional Sum					
Procurement Item Details					
SL. No	Item Description	Unit	Quantity	Unit Rate(in NPR)	Amount(in NPR)
1	Carry out additional test for material and works as required and instructed by the site incharge .	PS	1	15000	15000
2	Insurance	PS	1	35000	35000
3	Project Information Board	PS	1	2000	2000
4	Medium quality HDP pipe and junction boxes installation for Electrification work in slab as per technical specification. (Ground Slab)	PS	1	12000	12000

2 Construction work


2.1 Building completion work

Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
1	Site Clearance	Sqm	253.0			
2	Earthwork in excavation for preparation of-site and foundation work all Complete	Cum	132.24			
3	Earthwork in Filling work	Cum	233.16			
4	1st class Flat brick soling in foundation and floor including sand filling in joints, leveling , ramming etc. all complete	Sqm	266.0			
5	First Class local Chimney made brick work in cement sand mortar (1:6) in Foundation in Perfect line and level including wetting the bricks,packing the joints and curing all types of works as per specification and instruction by Engineer	Cum	51.42			
6	First Class local Chimney made brick work in cement sand mortar (1:4) in Superstructure in Perfect line and level including wetting the bricks,packing the joints and curing all types of works as per specification and instruction by Engineer	Cum	8.63			
7	Plain cement concret PCC M10. (1:3:6) work in foundation and floors with cement,sand and crussed aggregate of 10 mm to 38mm gauge including mixing with mixtere machin & compaction by vibrator ,laying in line & level with curing all type of works complete as per specification & instruction	Cum	5.34			

3

लक्ष्मी कुमार साह
सब-इन्जिनियर
योजना शाखा प्रमुख

(Handwritten signature)



Procurement Item

SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
8	Plain cement Concrete (PCC) in 1:2:4 ratio (M15) for RCC works in column, beam, slab etc. with approved quality of cement, sand and stone aggregate including mixing, laying, compacting and curing etc all complete as per design, drawing and specification.	Cum	14.53			
9	Plain cement Concrete (PCC) in 1:1.5:3 ratio (M20) for RCC works in column, beam, slab etc. with approved quality of cement, sand and stone aggregate including mixing, laying, compacting and curing etc all complete as per design, drawing and specification.	Cum	92.33			
10	Steel reinforcement bar of Fe 415/500 grade including straightening, cleaning, cutting, bending, placing in position and binding with annealed binding wire all complete as per design, drawing and specification.	Kg	9892.01			
11	Formwork, shuttering, centering with plywood and wooden post necessary propping, scaffolding, staging, supporting and removal etc all complete in perfect line and level as per design, drawing and specification.	Sqm	679.99			

लक्ष्मी कुमार साह
सब-इन्जिनियर
योजना शाखा प्रमुख